

BCS

2300°F Fire Bricks

BEFORE USING YOUR NEW BRICKS:

All fire bricks must be completely dried prior to firing. The bricks come from the factory partially fired, and can easily have absorbed moisture in shipment and storage.

- Carefully place the new bricks in an oven and heat to about 190° F. for a period of not less than 12 hours. DO NOT EXCEED 212° F or cracking may result.
- Slowly fire the bricks to full operating temperature after installation in your furnace or forge. Here is a firing schedule that has proved successful:
 1. Run the burner for 3 minutes.
 2. Turn off the burner and wait 5 minutes.
 3. Run the burner for 5 minutes.
 4. Turn off the burner and wait 5 minutes.
 5. Run the burner for 10 minutes.
 6. Turn off the burner for 5 minutes.
 7. Run the burner for 30 minutes.
 8. Turn off the burner and allow to slowly cool to room temperature.